

The PV Trends in developing countries



Miguel A. Egado Aguilera


Instituto de Energía Solar - Universidad Politécnica de Madrid

Some Facts about PV Rural Electrification

- ❑ Over the last decades PV has shown its potential as a technology for decentralized rural electrification in developing countries.
- ❑ PV systems are now being integrated in large rural electrification programs in different parts of the world.
- ❑ Programmes and studies now address the issues related to large-scale market development in rural areas:
 - Access to affordable credit,
 - local market infrastructure for installing and servicing PV systems, and
 - mechanisms for conducive local policy-making.
- ❑ the impact of the application of solar PV for rural electrification is more substantial than generally recognized
- ❑ In many countries, the growth rate of solar rural electrification exceeds that of conventional electrification with diesel microgrids or extension of the main grid.
- ❑ Lack of statistics on PV rural electrification

Trends in PV off-grid system technology

- ❑ Charge regulator with Maximum Power Point Tracking
- ❑ Bidirectional inverter: Battery charger and inverter
- ❑ PV modules designed for grid connected installations
- ❑ PV Hybrid systems




TECHNICAL STATUS OF PV RURAL ELECTRIFICATION

High growth rate of PV installations

Development of PV components poorly coordinated

Balance of System complexity underestimated

Mediocre Installations



QUALITY CONTROL

- Standardisation
- Certification:
 - System
 - PV Components
 - Installation



Main Faults observed

Shadows on the modules

PV components bad placed

Low initial state of charge in the batteries

Charge regulators:

- Lack of protections
- inadequacy with the battery

Wiring

- insufficient cross section
- no polarity identification

Lamps

- Premature fade-out of the tube
- insulation faults

Electromagnetic interferences

PV Rural Electrification project evaluation

- ✓ Finished this year
- ✓ Investment: 10 millions €
- ✓ Total Power Installed: 440 kWp
- ✓ Number of PV systems: 430
- ✓ Peak Power per system: 800 – 1200 Wp
- ✓ Use: Electricity for Schools and Health Centers

PV Modules and Structures 1



Short-circuit current 20 % higher than specified

PV Modules and Structures 2



Shadows

Easy to steal



Batteries



Paralell configuration

Connections not well tight



Charge controller 1




12 V subsystems



Two charge controllers
and inverter per
subsystem

Charge controller 2

Manufacturer's manual



de



Lamps and wiring



Social acceptance of PV technology



Lessons learnt from this project

- ✓ Good quality in B.O.S. components and acceptable PV modules
- ✓ Mistakes on systems design
- ✓ Lack of knowledge in quality control procedures
- ✓ Defective commissioning procedure
- ✓ Lack of users training

Our Quality Control approach

Certification process accessible to local markets

- Main end-users
- technical sophistication is not a synonym of quality improvement
- Installation and maintenance are local activities

Standardisation: ***Universal Technical Standard for Solar Home System***


- Prescriptions for:
 - PV components
 - Installation
 - PV system

Certification: ***Solar Home System Test Procedures***

- Standard Compliance Certificate
- Test for DC/AC Stand-Alone converters

Commissioning: ***Guidelines***

O&M and evaluation: ***Guidelines***



Some examples of application

- **PVMTI:** Morocco, India and Kenya
- **ADEME:** Burkina Fasso and Mauritania
- **Filipinas:** National Power Corporation
- **DANIDA:** Malawi, Ghana, Mozambique and Nepal
- **Perú:** GEF project (4600 SHS)
- **Bolivia:** Technical specification NB 1056

General conclusions



Taquile Island – Titicaca Lake (Peru)

- ✓ PV Stand Alone Systems Technology is not fully reliable yet
- ✓ Certification process must be accessible to local markets
 - Norms with low flexibility can be detrimental for the local markets development
 - increase of the technological dependence
- ✓ Sustainability of PV rural electrification projects is improved when the technical quality is reinforced
 - reliability of PV systems would be enhanced
 - availability, safety and maintainability are strongly dependents of non-technical factors.

- ✓ Improving quality means improving electricity service for final users

Thank you for your attention

